

## Base Bid

Item	Stand	Units	Unit Price	Qty	Total
104.01	TRAFFIC CONTROL	LS	\$55,000.00	1	\$55,000.00
200.01	MOBILIZATION/DEMObILIZATION	LS	\$55,000.00	1	\$55,000.00
202.01	REMOVE ASPHALT PAVEMENT	SY	\$3.43	4784	\$16,418.69
202.02	REMOVE SIDEWALK	SY	\$6.96	1120	\$7,798.56
208.01	CSLM (CONTROLLED LOW STRENGTH MATERIAL) CLASS II	CY	\$60.00	432	\$25,920.00
302.01	TYPE II AGGREGATE BASE	TN	\$14.30	43	\$614.90
402.01	PLANTMIX BITUMINOUS PAVEMENT	TN	\$108.17	750	\$81,130.50
613.01	CONCRETE SIDEWALK	SY	\$42.57	1120	\$47,678.40
637.01	DUST CONTROL	LS	\$40,000.00	1	\$40,000.00
900.01	24" X 48" TRENCH (STANDARD NPC) TRENCH – PARTIAL ROCK	LF	\$16.65	12895	\$214,753.33
900.02	24" X 12" ADDITIONAL TRENCH DEPTH 5' TO 8' – PARTIAL ROCK	LF	\$4.33	29076	\$126,015.38
900.03	CONCRETE ENCAsEMENT LOW PSI (150-300 PSI)	CU YD	\$160.50	1518	\$243,640.52
900.04	SUPPLY & INSTALL. 6" PVC CONDUIT	DUCT/FT	\$7.67	52934	\$405,844.98
900.05	SUPPLY & INSTALL 6" 45DEG.-48" RAD RIGID STEEL BEND	EA	\$470.83	46	\$21,658.32
900.06	SUPPLY & INSTALL 6" 90DEG.-48" RAD RIGID STEEL BEND	EA	\$470.83	17	\$8,004.16
900.07	MANHOLE (RS-94)	EA	\$7,447.96	18	\$134,063.23
900.08	MANDREL CONDUIT (IN EXISTING)	EA	\$0.52	52934	\$27,366.88
900.09	INSTALL MULE TAPE IN CONDUIT (IN EXISTING)	EA	\$0.48	52934	\$25,620.06
					<b>\$1,536,527.90</b>

## Alt Bid 1

Item	Stand	Units	Unit Price	Qty	Total
104.01	TRAFFIC CONTROL	LS	\$800.00	1	\$800.00
200.01	MOBILIZATION/DEMObILIZATION	LS	\$800.00	1	\$800.00
637.01	DUST CONTROL	LS	\$575.00	1	\$575.00
900.01	24" X 48" TRENCH (STANDARD NPC) TRENCH – PARTIAL ROCK	LF	\$16.65	471	\$7,844.03
900.02	24" X 12" ADDITIONAL TRENCH DEPTH 5' TO 8' – PARTIAL ROCK	LF	\$4.33	1340	\$5,807.56
900.03	CONCRETE ENCAsEMENT LOW PSI (150-300 PSI)	CU YD	\$160.50	35	\$5,617.54
900.05	SUPPLY & INSTALL. 6" PVC CONDUIT	DUCT/FT	\$7.67	471	\$3,611.16
900.06	SUPPLY & INSTALL 6" 90DEG.-48" RAD RIGID STEEL BEND	EA	\$470.83	2	\$941.67
900.08	MANDREL CONDUIT (IN EXISTING)	EA	\$0.52	471	\$243.51
900.09	INSTALL MULE TAPE IN CONDUIT (IN EXISTING)	EA	\$0.48	471	\$227.96
					<b>\$26,468.42</b>

## Alt Bid 2

Item	Stand	Units	Unit Price	Qty	Total
104.01	TRAFFIC CONTROL	LS	\$4,200.00	1	\$4,200.00
200.01	MOBILIZATION/DEMObILIZATION	LS	\$4,200.00	1	\$4,200.00
637.01	DUST CONTROL	LS	\$3,000.00	1	\$3,000.00
900.01	24" X 48" TRENCH (STANDARD NPC) TRENCH – PARTIAL ROCK	LF	\$16.65	1215	\$20,234.61
900.02	24" X 12" ADDITIONAL TRENCH DEPTH 5' TO 8' – PARTIAL ROCK	LF	\$4.33	3700	\$16,035.80
900.03	CONCRETE ENCAsEMENT LOW PSI (150-300 PSI)	CU YD	\$160.50	152	\$24,396.15
900.06	SUPPLY & INSTALL. 6" PVC CONDUIT	DUCT/FT	\$7.67	4305	\$33,006.44
900.07	MANHOLE (RS-94)	EA	\$7,447.96	1	\$7,447.96
900.08	MANDREL CONDUIT (IN EXISTING)	EA	\$0.52	4305	\$2,225.69
900.09	INSTALL MULE TAPE IN CONDUIT (IN EXISTING)	EA	\$0.48	4305	\$2,083.62
					<b>\$116,830.26</b>