

Mayor
Michael L. Montandon

City Manager
Gregory E. Rose

Council Members
William E. Robinson
Stephanie S. Smith
Shari Buck
Robert L. Eliason

Utilities Department - Technical Services Division
2829 Fort Sumter Dr. • North Las Vegas, Nevada 89030
Telephone: (702) 633-1484 • Fax: (702)399-0383 • TDD: (800) 326-6868
www.cityofnorthlasvegas.com

ADDENDUM NO. 3
BID NO. 1341
WATER BOLSTERING PROJECT BETWEEN NORTH 5TH AND DONNA
ISSUE DATE: 6/4/09

THE BIDDER SHALL ACKNOWLEDGE RECEIPT OF THIS ADDENDUM UNDER THE FIRST ADDENDUM LINE ON THE FIRST PAGE OF THE BID PROPOSAL.

1.0 CLARIFICATION on the response to Comment 7 in Addendum 2 the response stated that “Since all of the pavement is to be removed and replaced, the T-trench will not be required. Also per the Plate No.6B the regarding the Pipe Zone note, Control Low Strength Material (CLSM) will not be allowed in this application”.

The clarification is referencing Standard Drawing 503 that granular backfill or select back or Control Low Strength Material (CLSM) can be used above the pipe zone. In the pipe zone per Uniform Design and Construction Standards (UDACS) Plate No. 6B Control Low Strength Material (CLSM) will not be allowed.

2.0 CLARIFICATION on the response to Comment 14 in Addendum 2 the response stated that “Yes, section 104.04 Maintenance of Traffic paragraph “g” applies in this Project.” A contractor asked whether the 6 foot non-climb fence applies during the construction. Yes the 6 foot non-climb fence is required during construction.

CURT KROEKER, P.E.
Associate. Engineer/Utilities